

TPM 21069  
ER 07-19-005



## **Fire Protection Plan/Fuel Management Plan**

**For APN 519-094-16/TPM 21069**

Sajady TPM/ER 07-19-005

3551 Babel Drive

**Prepared By**

**Lamont Landis**

**Lamont Landis Consulting**

**43242 Modena Dr.**

**Temecula Ca. 92592**

**760-702-4370 [Lamontlandis@adelphia.net](mailto:Lamontlandis@adelphia.net)**

Prepared For the County of San Diego

**January 12, 2009 Revised February 17, 2010**

Principal Author

Lamont Landis

A handwritten signature in black ink, appearing to read 'Lamont Landis', written over a horizontal line.



## SAN DIEGO RURAL FIRE PROTECTION DISTRICT

August 25, 2010

County of San Diego  
Department of Planning and Land Use  
5201 Ruffin Road, Suite B  
San Diego, CA 92123-1666

Re: TPM 21069 Rev. 2/17/2010

Dear Planner,

The San Diego Rural Fire Protection District has reviewed the fire protection plan submitted by Lamont Landis Consulting Inc. The plan meets the objectives of the California Fire Code 2007 edition, Chapter 47 "Requirements for Wildland-Urban Interface (UWI) Areas" as well as the Fire Districts requirements for discretionary projects. Please call me directly with any questions that you may have.

Sincerely,

Cal Hendrie  
Battalion Chief /  
Fire Marshal

## **TABLE OF CONTENTS**

<b><u>CHAPTER 1 INTRODUCTION</u></b>	<b>PAGE 1</b>
<b><u>1.1 Project Location, Description and Environmental Setting</u></b>	
1.1.1 Project Location	2
1.1.2 Project Description	2
1.1.3 Environmental Setting	2
<b><u>CHAPTER 2 GUIDELINES FOR THE DETERMINATION OF SIGNIFICANCE</u></b>	<b>3</b>
<b><u>CHAPTER 3 ANTICIPATED FIRE BEHAVIOR IN THE VICINITY</u></b>	<b>4</b>
<b><u>CHAPTER 4 ANALYSIS OF PROJECT EFFECTS</u></b>	<b>4</b>
4.1 Adequate emergency services	4
4.2 Access	5
4.3 Water	
4.3.1 Water Service Availability	5
4.4 Ignition Resistant Construction and Fire Protection Systems	5
4.5 Fire Fuel Assessment	6
4.6 Fire Behavior Modeling	6
4.7 Defensible Space and Vegetation Management	7
4.8 Cumulative Impact Analysis	10
<b><u>CHAPTER 5 MITIGATION MEASURES AND DESIGN CONSIDERATIONS</u></b>	<b>10</b>
<b><u>CHAPTER 6 CONCLUSION</u></b>	<b>10</b>
<b><u>CHAPTER 7 LIST OF PREPARERS AND PERSONS AND ORGINAZATION CONTACTED</u></b>	<b>11</b>
<b><u>CHAPTER 8 REFERENCES</u></b>	<b>11</b>
<b>APPENDIX</b>	<b>12</b>

## EXECUTIVE SUMMARY

The proposed project is TPM 21069 to subdivide an 8.0 acre parcel into 3 parcels. The project is located at 3551 Babel Drive, Jamul (see Appendix E). The project encompasses gentle sloped land covered with Diego Coastal Sage Scrub. The surrounding property is urban developed with Diegan Coastal Sage Scrub and some non-native grasses. Removal of the vegetation for this project will be a marked improvement; it will substantially reduce the fire hazard in the area. The nearest fire protection for this project is San Diego Rural Fire Protection District Fire Station No. 36 and is less than 6.94 minutes away. Access to this project will be Babel Drive, which connects to Skyline Truck Trail. This Fire Protection Plan is in response to a request from the San Diego Rural Fire Protection District and the County of San Diego DPLU.

### Chapter 1 Introduction

This Fire Protection Plan/Fuel Modification Plan (FPP) has been prepared for Muchtar Sajady for a lot split with 3 parcels. The purpose of the Fire Protection Plan is to assess the potential impacts resulting from wildland fire hazards and identify the measures necessary to adequately mitigate those impacts. As part of the assessment this plan has considered the property location, topography, geology, combustible vegetation (fuel types), climatic conditions and fire history. The plan addresses water supply, access (including secondary/emergency access where applicable), structural ignitability and fire resistive building features, fire protection systems and equipment, impacts to existing emergency services, defensible space and vegetation management. The plan identifies and prioritizes areas for hazardous fuel reduction treatments and recommends the types and methods of treatment that will protect one or at risk communities and essential infrastructures. The plan recommends measures that property owners will take to reduce the probability of ignition of structures throughout the area addressed by the plan. This plan has been developed to protect the residential structures from potential radiant heat from wildfire hazards to the maximum extent practical. This plan does not guarantee that the structure will not burn, but greatly reduces that possibility. These are not shelter in place residences. A multitude of factors have been incorporated into the Fuel Modification Plan including wildfire history, prevailing wind patterns, existing vegetation /fuel loading, terrain and adjacent vegetation/land use.

Note: Title 14 requirements in State Responsibility Areas make fire requirements a multi-jurisdictional issue among the local fire authorities which include San Diego Rural Fire Protection District, CAL FIRE Unit Chief and the San Diego County DPLU (planning authority having jurisdiction implementing Title 14).

## Project Location, Description and Environmental Setting

### 1.1.1 Project Location

This project is located near the Community of Jamul and is in the San Diego Rural Fire Protection District response area. The project is located at 3551 Babel Drive, Jamul.

### 1.1.2 Project Description

This project is within the San Diego Rural Fire Protection District emergency response area. The project consists of approximately 8 acres, the APN# is 519-094-16. The sizes of the structures are undetermined at this time. The type of occupancy will be single-family residences. The proposed potential use of the new parcels will be residential. There will be an onsite steep slope easement on Parcel 3. There will be off site improvement to the roads; Babel Drive will be improved from Lot 1 to Dropseed Terrace to 24 ft AC on 28 ft graded. Note: TM 5213 will be responsible for improvements from Dropseed Terrace to Skyline Truck Trail.

### 1.1.3 Environmental Setting

The site was visited on August 22, 2008 by Lamont Landis

#### Topography

The project encompasses gentle sloped land with the elevations onsite ranging between approximately 1,450 to 1,575 feet above sea level.

Vegetation types are some non-native grass and mostly Diegan Coastal Sage Scrub.

Fuel loads: The property is covered with Diego Coastal Sage Scrub approximately three feet in height. The fuel load for this type of fuel will be approximately 3.6 tons per acre (RMRS-GTR-153 USDA Forest Service).

The Harris Fire burned in the area but not on the site. The Harris Fire started on October 21, 2007 at Harris Ranch Road and Highway 94 in Portrero; 90,440 acres were burned. The fire injured 21 civilians and 36 firefighters, five people died as result of the fire. Two hundred eleven homes and 262 outbuildings were destroyed, 259 structures were damaged. Embers from the wildfire traveled long distances due to Santa Ana winds and low humidity. The Harris Fire was driven by Santa Ana winds fueled by 50-year old brush and an extended drought.

The following scenarios are typical of the area and are to be considered worst case assumptions:

#### **Summer**

South, Southwest, Northwest and West wind condition can result in the following fuel moistures.

1-hour fuel moisture.....4%  
10-hour fuel moisture.....6%  
100-hour fuel moisture.....8%  
Live woody fuel moisture.....80%

#### **Fall**

South, Southwest, Northwest and West wind condition can result in the following fuel moistures.

1-hour fuel moisture.....2%  
10-hour fuel moisture.....3%  
100-hour fuel moisture.....5%  
Live woody fuel moisture.....50%

#### **Santa Ana Wind Condition two to four times a year.**

1-hour fuel moisture .....2%  
10-hour fuel moisture.....3%  
100- hour fuel moisture.....5%  
Live woody fuel moisture.....50%

The ownership of the area is private. Onsite vegetation consists of non-native dry climate grasses and Diegan Coastal Sage Scrub, west of the property consist of private property and open space easements granted to the County of San Diego.

### **Chapter 2 GUIDELINES FOR THE DETERMINATION OF SIGNIFICANCE**

The project is located next to some wildland areas with urban developed lands; however the new structure will be separated from the native vegetation by more than 100 feet of modified fuel selected from the San Diego County acceptable plant list. The project has paved roads through developed land to adequately egress the site. The access road to the proposed single family dwellings is less than 1,300 feet from a point of egress in two directions at the intersection of Dropseed Terrace and Babel Drive, and meets the San Diego County threshold of 1,320 feet for parcels 1 to 4.99 acres. The access on Babel Drive to Skyline Truck Trail is 1800 ft. and one of two means of egress.(See appidix G) The existing and new roads and driveways will support fire apparatus for access. The project will result in adequate emergency access. The project will not adversely affect the fire district. The water supply with existing and additional fire hydrants will serve the project and meet the requirements of the San Diego Rural Fire Protection District and the County of San Diego.

### **Chapter 3 ANTICIPATED FIRE BEHAVIORS IN THE VICINITY**

The anticipated fire behavior onsite is not expected to be significant. Flames in the unmodified non-native grasses will be approximately 12.7 feet in height. The proper clearance of 30 feet next to the road sides should allow for egress in the event of a fire (non-native grasses with 12.7 foot max flame length). The flame length from the unmodified Diegan Coastal Sage Scrub will be approximately 52.9 feet. The offsite unmodified vegetation to the northeast will produce a large front of fire and covers miles of mountainous terrain with native vegetation. The removal of vegetation in the Fuel Modification Zone will provide adequate protection from radiant heat from a large fire. The ember production from a large front will be significant but will be mitigated by the enhanced construction in Chapter 7 A of the County Building Code. The off site urban developed (rural in nature) property should permit egress all the way to Skyline Truck Trail. The new structures will be 100 feet from this unmodified vegetation and mitigated by enhanced wildland urban interface construction as per Chapter 7A San Diego County Building Code. The project will meet the requirements of the California Fire Code, California Code of Regulations Title 14 (enforced by San Diego County DPLU), County Fire Code and the County Consolidated Fire Code.

### **Chapter 4 ANALYSIS OF PROJECT EFFECTS**

The development of this area will reduce the spread of a wildfire by reducing the fuel loading, along with the existing and new water supply and fire hydrants; improving of roads in the project and clearing of the home site will provide additional fuel breaks in the area, this will be a major fuel break that will buffer and slow down a fire in the area. The Sajady Development will fall within the guidelines of the San Diego County General Plan for emergency response time objectives.

#### **4.1 Adequate Emergency Services**

Initial Fire Department response is from San Diego Rural Fire Department Station No. 36 which is located at 14047 Maxfield, this station is staffed by 3 firefighters (two full-time paid and one volunteer), 24 hours a day 7 days a week. Apparatus include one type-two engine, one type-three engine and one rescue truck. The station is located less than 3.21 miles from the above property and is less than 6.94 minutes away by using the estimated timetable in NFPA 1142.

#### **4.2 Fire Access**

The proposed fire access road is designed to allow for egress for the public and fire fighting access for the Fire Department. The on site road Babel Drive will be improved to 24 feet paved AC or better. The fuel modification on or adjacent to the road adds to the reduction of the spread of the fire and is part of the overall Fuel Modification Plan. All new roads and driveways shall have a minimum clearance of 30 feet on each side. Turnarounds shall comply with Appendix B. Angle of approach shall not exceed 7 Deg. The proposed access roads shall meet or exceed all San Diego County DPLU and San Diego Rural Fire Protection District requirements. All roads and driveways shall be all-weather surface suitable for travel by a 50,000 lb. fire apparatus. All driveways or roads that exceed 15% of grade will be Portland Cement Concrete with a deep broom finish perpendicular to the direction of travel to enhance traction; no grade will exceed 20% of grade. The primary access for this project is Babel Drive which will have a 36 ft. radius cul-de-sac at Parcel 1. Babel Drive is 20 ft wide to Skyline Truck Trail and meets Title 14 at 18 ft but not the San Diego County Fire Code at 24 ft. This project will be responsible for the widening of the road to 24 feet paved to Dropseed Terrace. TM 5213 rpl-1 is already responsible for widening the road Babel Drive to 24 feet paved from Dropseed Terrace to Skyline Truck Trail. Street signs shall be posted as per the County Standard (DS-13).

Egress from the project will comply with San Diego County standards. All roads are less than 1,320 feet from the point of egress in two directions, which meets the requirement for 1 to 4.99 acre parcels. Access from the project will be Babel Drive to Skyline Truck Trail which is 1,800 ft; however a second access at 1,300 ft is Babel Drive to Dropseed Terrace that continues on to Sleep Willow Lane to Hidden Trail Drive Skyline Truck Trail. (See map TM 5213 rpl-1 Appendix G)

### **4.3 Water**

#### **4.3.1 Public Water**

The water supply for this proposed project will come from existing water mains. The water supply will come from the Otay Water District. The minimum required fire flow for this project will be 2500 GPM @ 20 PSI residual (see Appendix I). A proposed fire hydrant will be located at the southwest corner of Parcel #1 and will serve all three parcels. The new fire hydrant located at the southwest corner of Parcel #1 and the calculated fire flow is 900 Gallons per minute @ 0 psi. The fire flow calculation for the existing fire hydrant at the corner of Bonita Vista Way is 854@ 20 psi. The fire flow is below the required 2,500 gallons per minute which would normally require water tanks. Water tanks were previously recommended for the site, it was suggested that the fire hydrant would be acceptable. This plan is proposing the fire hydrant with 900 gallons per minute instead of the water tank with 10,000 gallons of water. (The water tank can supply 900 gallons of water per minute for 11 minutes, where the fire hydrant can supply 900 gallons per minute of water for 2 hours minimum.)



#### **4.4 Ignition Resistant Construction and Fire Protection Systems**

All new structures shall be equipped with the following interface features:

1. Roofs will be a Class "A" noncombustible material and shall meet the DPLU standards.
2. Eaves and balconies will be of noncombustible material and meet the San Diego County Building Code and comply with the International Urban-Wildland Interface Code 2006 Edition.
3. Exterior walls will be a noncombustible or ignition resistive material and meet the San Diego County Building Code Chapter 7A.
4. All habitable structures and attached garages will be equipped with automatic fire sprinklers per the County Consolidated Fire Code requirements (NFPA-13D). All sprinkler systems shall be approved by the San Diego Rural Fire Protection District prior to installation.
5. All future outbuildings must be approved by the San Diego Rural Fire Protection District prior to installation.
6. All structures will comply with the wildland area structural requirements of the County Building Code Chapter 7A in affect at the time of a building permit application.

#### **4.5 Fire Fuel Assessment**

The site has the potential to experience a vegetation fire; this is based on the type of vegetation and its continuous nature, Santa Ana winds, high temperatures, low humidity and drought conditions. Onsite vegetation consists of Diegan Coastal Sage Scrub (Model sh7 (147) fuel). The surrounding property is urban developed to the south with some non-native grassland and is maintained on an annual bases. East of the property is mostly Diegan Coastal Sage with a small amount of grasses. North of the property is urban developed (Rural Developed) with agriculture and Diegan Coastal Sage Scrub; west of the property is urban developed (Rural Developed) and Diegan Coastal Sage Scrub.

#### **4.6 Fire Behavior Modeling**

##### **BehavePlus Wildfire Modeling**

The BehavePlus Fire Modeling System (Version 4.0.0) developed by the U.S. Forest Service Rocky Mountain Research Station is the generally accepted software for modeling large-scale wildfire behavior and characteristics. The BehavePlus System was designed to evaluate a variety of wildfire variables for large wildland fires including surface fire spread, safety zones, fire containment, spotting distance crown scorch and probability of ignition. Two aspects of this program (surface fire spread and safety zone) have been utilized to assist in determining acceptable fuel modification requirements. The

BehavePlus Program coupled with onsite and surrounding area vegetation, access, slope and weather conditions are the basis for the following.

The BehavePlus Fire System has been run for the following worst case scenarios:

60 MPH wind, 100-degree ambient air temperature, 2 % dead fuel moisture, 50 % live fuel moisture and 50% max slope with 25 % average slope aspect. The model was run for four fuel model scenarios, as the project contains varying types of fuels.

It should be noted that the BehavePlus Model does not and cannot include all variables associated with a specific site and regime, and adjacent mixed land uses can influence the results.

The BehavePlus Model run results are summarized in Table 1.

**Table 1**

**BehavePlus Fire Model**

**Fuel Model SCAL18 [Sage /Buckwheat]**

Wind Speed & Direction	Mid-flame	Rate of Spread	Fire Line Intensity	Flame Length
60 mph N, NE, E	35.0 mph	387.4 Ch/h	30643 Btu/ft/s	52.1 ft.

Up-slope spotting distance= 3.4 miles

**Fuel Model Sh2 Moderate Load, Dry Climate Shrub (S) (142)**

Wind Speed & Direction	Mid-flame	Rate of Spread	Fire Line Intensity	Flame Length
60 mph N, NE, E	35 mph	205.9 Ch/h	5853 Btu/ft/s	24.3 ft

Up-slope spotting distance= 2.0 miles

The Behave Plus coupled with the expected offshore Santa Ana wind direction, anticipated down slope fire line aspect and relatively low fuel vegetation within the urban wildland interface areas, and existing fuel modified areas serves as a basis for formulation of the recommended Fuel Modification Zone locations.

#### **4.7 Defensible Space and Vegetation Management**

**Fuel Management Zones:**

Parcel 1, 2 and 3

As proposed the residential structure from the structure to a point 50 feet in all directions shall be maintained as Zone 1 and from a point 50 feet from the structure to 100 feet shall be maintained as Zone 2. Zones 1 and 2 shall be clearly and permanently marked for annual maintenance. Exception: The north side of the structure on Parcel #2 is 50 feet from the property line and will be cleared off site as per SDRFPD Ordinance 2005-01 for the Zone 2 clearance. All distances are on a horizontal plane regardless of the slope.

Note: The San Diego Rural Fire Protection District requires that vacant land be cleared to 100 feet from adjacent structures, Ordinance # 2005-01

Note: All Fuel Modification Zones must be delineated with permanent markers until such times as they are no longer needed as determined by the Fire Marshal. The most reliable markers are metal fence posts with a baked on painted finish (Day Glow Orange on the top half).

#### **Fuel Management Zone 1:**

Zone 1 is the first 50 feet or as otherwise indicated; this is an area where native vegetation has been removed, irrigated and planted with drought-tolerant and fire resistant plant material. Plant selection shall be from Appendix A, (The San Diego County Acceptable Plant List).

The purpose of Zone 1 (set back zone) is to provide a defensible space for fire suppression forces to protect structures from radiant and convective heat. The following shall be part of fuel management of this zone:

1. No combustible construction, groves, firewood, propane tanks, fuel or combustible native or ornamental vegetation shall be allowed within the 50 foot set back Zone 1 or within 30 feet of the edge of slopes.
2. Mature trees (>18') to be limbed up or canopied 6' to 8' from ground level.
3. No tree limbs within 10' of chimney outlets or dead limbs overhanging structures.
4. Spacing between mature tree canopies must be as follows:
  - A. Slopes 0-20 % ----10 Feet.
  - B. Slopes 21-40 % ----20 Feet.
  - C. Slopes > 41 % ----30 Feet.

The minimum horizontal space between the edges of shrubs

- A. Slopes 0-20%----2 times the height of the shrub.
- B. Slopes 21-40%----4 times the height of the shrub.
- C. Slopes > 40%----6 times the height of the shrub.

The minimum vertical space between the top of the shrub and the bottom of the lower tree braches is 3 times the height of the shrub.

(Gilmer, M. 1994 California Wildfire Landscaping, adapted by the State Board of Forestry and Fire Protection on February 8, 2006.)

## **Fuel Management Zone 2**

This Fuel Management Zone will be the area between 50 feet to 100 feet of the structure. The landscape plans shall include methods of erosion control to protect against slope failure. The following shall apply to Zone 2:

1. Clear 50% of the existing native combustible vegetation including all dead and dying. This area must be modified so combustible vegetation does not occupy more than 50% of the total square footage. Trees may remain provided that the horizontal distance between crowns of the adjacent trees is not less than 10 feet. All remaining native vegetation shall be maintained at a height of 18 inches on year round bases. Native grasses shall be maintained at a height of 4 to 6 inches on year round bases.
2. Orchards, groves and vineyards shall be maintained as per sec. 4707.3.2 of the San Diego County Fire Code adopted January 30, 2008.
3. Fire resistive plant materials are also required in Zone 2 to control soil erosion and/or to reduce vegetation mass near the wildland interface.
4. Plant spacing will be the same as noted for Zone 1.
5. All plants used in Zone 1 and 2 comply with the San Diego County Acceptable Plant List, Appendix A.

## **Landscape Requirements/Restrictions**

The landscaping within the Fuel Modification Zones must be approved by the San Diego Rural Fire Protection District and shall include low fuel, drought tolerant type vegetation from the list adopted by the County of San Diego (see Appendix A).

## **Fuel Modification Zone Maintenance Requirements**

Fuel Modification Zones must be maintained in a manner that will fulfill the intent of the Fuel Modification Plan and meet the requirements of the San Diego Rural Fire Protection District. Maintenance will include initial planting, weeding, irrigation installation, maintenance and plant pruning; removal of dead and down vegetation, and the replacement of plants as required.

The following will also apply to this project:

1. Each lot owner is personally responsible for all irrigation and landscaping Fuel Treatment Zones within their property boundaries.

2. The San Diego Rural Fire Protection District will hold each lot owner accountable for enforcement of all wildland fire protection issues discussed in this plan.
3. Each lot owner shall not allow trash dumping or disposal of any yard trimmings in the Fuel Treatment Zones.
4. The San Diego Rural Fire Protection District or its designated representative shall decide any disputes related to individual lot landscaping or fuel treatment, with respect to interpretation of the Fire Protection Plan. Decisions shall be final and binding on the lot owner.
5. Should modifications to the Tentative Map Plans occur, any and/or all of the Fire Protection Plan may be revised at the discretion of the San Diego Rural Fire Protection District.
6. All exterior boundaries of Zones 1 and 2 shall be permanently marked on the ground for purposes of guiding annual fuel management maintenance and inspection operations. The most reliable markers are steel fence post with a baked on painted finish. The upper half of the above ground portion of the fence post is then painted a bright "day glow" orange to improve visibility. These Fuel Treatment Zone markers must be spaced so that the markers on each side of an installed marker can be seen from that marker.

#### **4.8 Cumulative Impact Analysis**

This and other projects may have a cumulative impact on the ability to protect residences from wildfires. Over time with this project and other development in the area the population in rural areas will increase, which may increase the chances of a wildfire and increase the number of people and structures exposed to the risk of loss, injury or death.

Property taxes and other currently applicable fees generated by the project may not adequately fund fire services. This project is required to participate in CDF 04-1 prior to the recordation of the parcel map or issuance of any permits.

### **Chapter 5 MITIGATION MEASURES AND DESIGN CONSIDERATIONS**

The fuel modification will reduce the threat to the structures from the vegetation onsite. The structure will be designed with enhanced fire resistive construction as per the County Building Code Chapter 7A. The driveway and access roads will have 30 feet of clearing (fuel modification) on both sides. The structure will have 100 feet of fuel modification. The fire hydrant and the on site road improvements will allow for fire fighting access.

### **Chapter 6 CONCLUSIONS**

The development of this area will reduce the spread of a wildfire by reducing the fuel loading, and the addition of water supply (additional hydrants for fire fighting @ 2500 gallons per minute at 20 psi residual); improving of roads in the project and the clearing

of home sites will provide additional fuel breaks in the area. A two tiered Fuel Modification Zone system is proposed to create an adequate fire safety buffer along the proposed development areas and access roads, which would be defensible space in case of a wildfire. The Fuel Modification Zone recommendations are based upon a combination of BehavePlus modeling data, onsite vegetation, access, surrounding area fuel conditions, slope and worst-case weather conditions. The Fuel Modification Zones have been designed to meet the requirements of the San Diego Rural Fire Protection District and San Diego County DPLU. The proposed mitigation will reduce the significance to a "less than significant" status in accordance with guidelines.

## **Chapter 7 LIST OF PREPARERS AND PERSONS AND ORGANIZATIONS CONTACTED**

Ron Ashman - Crew Engineering

David Nissen – Battalion Chief San Diego Rural Fire Protection District.

Lamont Landis - Principal Author (is on the San Diego County list of approved consultants).

## **Chapter 8 REFERENCES**

1. Behave: Fire Behavior Prediction and Fuel Modeling – Burn Subsystems. Part 1 General Technical Report INT-194. January 1986. Patricia L. Andrews USDA Forest Service, Intermountain Station, Ogden Utah, 84401.
2. Behave: Fire Behavior Prediction and Fuel Modeling- Burn Subsystem Part 2. General Technical Report INT-360. May 1989 Patricia L. Andrews and Carolyn H. Chase. USDA Forest Service. Intermountain Station, Ogden, Utah 84401.
3. BehavePlus Fire Modeling System, Version 3.02 Patricia L. Andrews, Collins D. Bevins and Robert C. Seli. US Forest Services, Rocky Mountain Research Station, Fire Sciences Laboratory. Missoula MT.
4. How to Predict the Spread and Intensity of Forest and Range Fires. General Technical Report INT-1943 May 1989. Richard C. Rothermel, USDA Forest Service Intermountain Station, Ogden Utah, 84401.
5. 2007 California Fire Code, California Code of Regulations Title 24 Part 9. Which is based on the 2006 International Fire Code,
6. County of San Diego Fire Code and Building Code and Amendments Effective January 30, 2008. Section 96.1.001
7. National Fire Protection Association NFPA 1142 Water Supplies for Suburban and Rural Firefighting 2001 Edition.
8. International Code Council Urban-Wildland Interface Code 2006 edition
9. Standard Fire Behavior Fuel Models: A Comprehensive Set For Use with Rothermel's Surface Fire Spread Model. Authors Joe H. Scott and Robert E. Burgan General Technical Report RMRS-GTR-153 USDA Forest Service Rocky Mountain Research Station.

10. Aids for Determining Fuel Models for Estimating Fire Behavior. By Hal E Anderson USDA Forest Service General Technical Report INT-122
11. General Guidelines for Creating Defensible Space Adopted by The State Board of Forestry and Fire Protection on February 8, 2008
12. USDA Forest service General Technical Report PSW-GTR-158. 1995 (Jack Cohen)

## **Appendix Table of Contents**

<b>Appendix A</b>	<b>Plant List</b>
<b>Appendix B</b>	<b>Fire Apparatus Turnaround</b>
<b>Appendix C</b>	<b>Photos</b>
<b>Appendix D</b>	<b>BehavePlus Fire Model</b>
<b>Appendix E</b>	<b>Street Name Change Letter</b>
<b>Appendix F</b>	<b>Project Facility Availability Fire</b>
<b>Appendix G</b>	<b>TM 5213 RPL-1 Map</b>
<b>Appendix H</b>	<b>Vegetation Map</b>
<b>Appendix I</b>	<b>Otay Water District Flow Letter</b>
<b>Appendix K</b>	<b>Fuel Modification Map</b>



---

## **Appendix A**

### **Undesirable Plan List**

### **Acceptable Plants for a Defensible Space In Fire Prone Areas**

# SUGGESTED PLANT LIST FOR A DEFENSIBLE SPACE

BOTANICAL NAME	COMMON NAME	Climate Zone
<b>TREES</b>		
Acer		
platanoides	Norway Maple	M
rubrum	Red Maple	M
saccharinum	Silver Maple	M
saccarum	Sugar Maple	M
macrophyllum	Big Leaf Maple	C/ (R)
Alnus rhombifolia	White Alder	C/I/M (R)
Arbutus		
unedo	Strawberry Tree	All zones
Archontophoenix		
cunninghamiana	King Palm	C
Arctostaphylos spp.**	Manzanita	C/I/D
Brahea		
armata	Blue Hesper Palm	C/D
edulis	Guadalupe Palm	C/D
Ceratonia siliqua	Carob	C/I/D
Cercidium floridum	Blue Palo Verde	D
Cercis occidentalis**	Western Redbud	C/I/M
Cornus		
nuttallii	Mountain Dogwood	I/M
stolonifera	Redtwig Dogwood	I/M
Eriobotrya		C/I/D
japonica	Loquat	C
Erythrina caffra	Kaffirboom Coral Tree	I/M
Ginkgo biloba "Fairmount"	Fairmount Maidenhair Tree	I/D/M
Gleditsia triacanthos	Honey Locust	
Juglans		I
californica	California Walnut	C/I
hindsii	California Black Walnut	I/D/M
Lagerstroemia indica	Crape Myrtle	I
Ligustrum lucidum	Glossy Privet	C/I/M
Liquidambar styraciflua	Sweet Gum	I
Liriodendron tulipifera	Tulip Tree	
Lyonothamnus floribundus		C
ssp. Asplenifolius	Fernleaf Catalina Ironwood	C/I/D
Melaleuca spp.	Melaleuca	C/I
Parkinsonia aculeate	Mexican Palo Verde	
Pistacia		
chinensis	Chinese Pistache	
	Pistachio Nut	C/I/D

vera  
 Pittosporum  
   phillyraeoides  
   viridiflorum  
 Platanus  
   acerifolia  
   racemosa\*\*  
 Populus  
   alba  
   fremontii\*\*  
   trichocarpa  
 Prunus  
   xblireiana  
   caroliniana  
   ilicifolia\*\*  
   lyonii\*\*  
   serrulata 'Kwanzan'  
   yedoensis 'Akebono'  
 Quercus  
   agrifolia\*\*  
   engelmannii  
   \*\* suber  
 Rhus  
   lancea\*\*  
   Salix spp.\*\*  
 Tristania conferta  
 Ulmus  
   parvifolia  
   pumila  
 Umbellularia californica\*\*

# Pistachio Nut

Willow Pittosporum  
 Cape Pittosporum  
  
 London Plane Tree  
 California Sycamore  
  
 White Poplar  
 Western Cottonwood  
 Black Cottonwood  
  
 Flowering Plum  
 Carolina Laurel Cherry  
 Hollyleaf Cherry  
 Catalina Cherry  
 Flowering Cherry  
 Akebono Flowering Cherry  
  
 Coast Live Oak  
 Engelmann Oak  
 Cork Oak  
  
 African Sumac  
 Willow  
 Brisbane Box  
  
 Chinese Elm  
 Siberian Elm  
 California Bay Laurel

I  
  
 C/I/D  
 C/I  
  
 All zones  
 C/I/M  
  
 D/M  
 I  
 I/M  
  
 M  
 C  
 C  
 C  
 M  
 M  
  
 C/I  
 I  
 C/I/D  
  
 C/I/D  
 All zones (R)  
 C/I  
  
 I/D  
 C/M  
 C/I

# SHRUBS

Agave	Century Plant	D
americana	Century Plant	D
deserti	Shawis Century Plant	D
shawii**		
Amorpha fruticosa**	False Indigobush	I
Arbutus		
menziesii**	Madrone	C/I
Arctostaphylos spp.**	Manzanita	C/I/D
Atriplex**		
canescens	Hoary Saltbush	I
lentiformis	Quail Saltbush	D
Baccharis**		
glutinosa	Mule Fat	C/I
pilularis	Coyote Bush	C/I/D
Carissa grandiflora	Natal Plum	C/I
Ceanothus spp.**	California Lilac	C/I/M
Cistus spp.	Rockrose	C/I/D
Cneoridium dumosum**	Bushrue	C
Comarostaphylis**		
diversifolia	Summer Holly	C
Convolvulus cneorum	Bush Morning Glory	C/I/M
Dalea		
orcuttii	Orcutt's Delea	D
spinosa**	Smoke Tree	I/D
Elaeagnus		
pungens	Silverberry	C/I/M
Encelia**		
californica	Coast Sunflower	C/I
farinose	White Brittlebush	D/I
Eriobotrya		
deflexa	Bronze Loquat	C/I
Eriophyllum		
confertiflorum**	Golden Yarrow	C/I
staechadifolium	Lizard Tail	C
Escallonia spp.	Escallonia	C/I
Feijoa sellowiana	Pineapple Guava	C/I/D
Fouquieria splendens	Ocotillo	D
Fremontodendron**		
californicum	Flannelbush	I/M
mexicanum	Southern Flannelbush	I
Galvezia		
juncea	Baja Bush-Snapdragon	C
speciosa	Island Bush-Snapdragon	C
Garrya		
elliptica	Coast Silktassel	C/I
flavescens**	Shiv. Silktassel	I/M

Heteromeles arbutifolia\*\*  
 Lantana spp.  
 Lotus scoparius  
 Mahonia spp.

Malacothamnus  
 clementinus

fasciculatus\*\*

Melaleuca spp.  
 Mimulus spp.\*\*  
 Nolina

parryi  
 parryi ssp. wolfii  
 Photinia spp.  
 Pittosporum

crassifolium  
 rhombifolium  
 tobira 'Wheeleri'  
 undulatum  
 viridiflorum

Plumbago auriculata

Prunus  
 caroliniana  
 ilicifolia\*\*  
 lyonii\*\*

Puncia granatum

Pyracantha spp.

Quercus  
 dumosa\*\*

Rhamus  
 alaternus  
 californica\*\*

Rhaphiolepis spp.

Rhus  
 integrifolia\*\*

laurina  
 lentii  
 ovata\*\*  
 trilobata\*\*

Ribes  
 viburnifolium  
 speciosum\*\*

Romneya coulteri

Rosa  
 californica\*\*  
 minutifolia

Ashy Silktassel I/M  
 Toyon C/I/M  
 Lantana C/I/D  
 Deerweed C/I  
 Barberry C/I/M

San Clemente Island Bush Mallow C

Mesa Bushmallow C/I

Melaleuca C/I/D  
 Monkeyflower C/I (R)

Parry's Nolina I  
 Wolf's Bear Grass D  
 Photinia All Zones

Queensland Pittosporum C/I  
 Wheeler's Dwarf C/I/D  
 Victorian Box C/I  
 Cape Pittosporum C/I  
 Cape Plumbago C/I/D

Carolina Laurel Cherry C  
 Hollyleaf Cherry C  
 Catalina Cherry C  
 Pomegranate C/I/D  
 Firethorn All Zones

Scrub Oak C/I

Italian Blackthorn C/I  
 Coffeeberry C/I/M  
 Rhaphiolepis C/I/D

Lemonade Berry C/I  
 Laurel Sumac C/I  
 Pink-Flowering Sumac C/D  
 Sugarbush I/M  
 squawbush I

Evergreen Currant C/I  
 Fuschia-Flowering Gooseberry C/I/D  
 Matilija Poppy I

Salvia spp.\*\*  
Sambucus spp.\*\*  
Symphoricarpos mollis\*\*  
Syringa vulgaris  
Tecomaria capensis  
Teucrium fruticans  
Toxicodendron\*\*  
    diversilobum  
Verbena  
    lilacina  
Xylosma congestum  
Yucca\*\*  
    schidigera  
    whipplei

California Wild Rose  
Baja California Wild Rose  
Sage  
Elderberry  
Creeping Snowberry  
Lilac  
Cape Honeysuckle  
Bush Germander  
  
Poison Oak  
  
Lilac Verbena  
Shiny Xylosma  
  
Mojave Yucca  
Foothill Yucca

C/I  
C/I  
All Zones  
C/I/M  
C/I  
M  
C/I/D  
C/I  
  
I/M  
  
C  
C/I  
  
D  
I

## GROUNDCOVERS

Achillea**	Yarrow	All Zones
Aptenia cordifolia	Apteria	C
Arctostaphylos spp.**	Manzanita	C/I/D
Baccharis**		
pilularis	Coyote Bush	C/I/D
Ceanothus spp.**	California Lilac	C/I/M
Cerastium tomentosum	Snow-in-Summer	All Zones
Coprosma kirkii	Creeping Coprosma	C/I/D
Cotoneaster spp.	Redberry	All Zones
Drosanthemum hispidum	Rosea Ice Plant	C/I
Dudleya		
brittonii	Brittonis Chalk Dudleya	C
pulverulenta**	Chalk Dudleya	C/I
virens	Island Live Fore-ever	C
Eschscholzia californica**	California Poppy	All Zones
Euonymus fortunei		
'Carrierei'	Glossy Winter Creeper	M
'Coloratus'	Purple-Leaf Winter Creeper	M
Ferocactus viridescens**	Coast Barrel Cactus	C
Gaillardia grandiflora	Blanket Flower	All Zones
Gazania spp.	Gazania	C/I
Helianthemum spp.**	Sunrose	All Zones
Lantana spp.	Lantana	C/I/D
Lasthenia		
californica**	Common Goldfields	I
glabrata	Coastal Goldfields	C
Lupinus spp.**	Lupine	C/I/M
Myoporum spp.	Myoporum	C/I
Pyracantha spp.	Firethorn	All zones
Rosmarinus officinalis	Rosemary	C/I/D
Santolina		
chamaecyparissus	Lavender Cotton	All Zones
virens	Santolina	All Zones
Trifolium frageriferum	O'Connor's Legume	C/I
Verbena		
rigida	Verbena	All Zones
Viguiera laciniata**	San Diego Sunflower	C/I
Vinca		
minor	Dwarf Periwinkle	M

## VINES

Antigonon leptopus	San Miguel Coral Vine	C/I
Distictis buccinatoria	Blood-Red Trumpet Vine	C/I/D
Keckiella cordifolia**	Heart-Leaved Penstemon	C/I
Lonicera		
japonica 'Halliana'	Hall's Honeysuckle	All Zones
subspicata**	Chaparral Honeysuckle	C/I
Solanum		
jasminoides	Potato Vine	C/I/D

## PERENNIALS

Coreopsis		
gigantea	Giant Coreopsis	C
grandiflora	Coreopsis	All Zones
maritime	Sea Dahlia	C
verticillata	Coreopsis	C/I
Heuchera maxima	Island Coral Bells	C/I
Iris douglasiana**	Douglas Iris	C/M
Iva hayesiana**	Poverty Weed	C/I
Kniphofia uvaria	Red-Hot Poker	C/M
Lavandula spp.	Lavender	All Zones
Limonium californicum		
var. mexicanum	Coastal Statice	C
perezii	Sea Lavender	C/I
Oenothera spp.	Primrose	C/I/M
Penstemon spp.**	Penstemon	C/I/D
Satureja douglasii	Yerba Buena	C/I
Sisyrinchium		
bellum	Blue-Eyed Grass	C/I
californicum	Golden-Eyed Grass	C
Solanum		
xanthii	Purple Nightshade	C/I
Zauschneria**		
californica	California Fuschia	C/I
cana	Hoary California Fuschia	C/I
'Catalina'	Catalina Fuschia	C/I

## ANNUALS

Lupinus spp.**	Lupine	C/I/M
----------------	--------	-------



## UNDESIRABLE PLANT LIST

The following species are highly flammable and should be avoided when planting within the first 50 feet adjacent to a structure. The plants listed below are more susceptible to burning, due to rough or peeling bark, production of large amounts of litter, vegetation that contains oils, resin, wax, or pitch, large amounts of dead material in the plant, or plantings with a high dead to live fuel ratio. Many of these species, if existing on the property and adequately maintained (pruning, thinning, irrigation, litter removal, and weeding), may remain as long as the potential for spreading a fire has been reduced or eliminated.

BOTANICAL NAME	COMMON NAME
<u>Abies species</u>	Fir Trees
<u>Acacia species</u>	Acacia (trees, shrubs, groundcovers)
<u>Adenostoma sparsifolium**</u>	Red Shanks
<u>Adenostoma fasciculatum**</u>	Chamise
<u>Agonis juniperina</u>	Juniper Myrtle
<u>Araucaria species</u>	Monkey Puzzle, Norfolk Island Pine
<u>Artemesia californica**</u>	California Sagebrush
<u>Bambusa species</u>	Bamboo
<u>Cedrus species</u>	Cedar
<u>Chamaecyparis species</u>	False Cypress
<u>Coprosma pumila</u>	Prostrate Coprosma
<u>Cryptomeria japonica</u>	Japanese Cryptomeria
<u>Cupressocyparis leylandii</u>	Leylandii Cypress
<u>Cupressus forbesii**</u>	Tecate Cypress
<u>Cupressus glabra</u>	Arizona Cypress
<u>Cupressus sempervirens</u>	Italian Cypress
<u>Dodonea viscosa</u>	Hopseed Bush
<u>Eriogonum fasciculatum**</u>	Common Buckwheat
<u>Eucalyptus species</u>	Eucalyptus
<u>Heterotheca grandiflora**</u>	Telegraph Plant
<u>Juniperus species</u>	Junipers
<u>Larix species</u>	Larch
<u>Lonicera japonica</u>	Japanese Honeysuckle
<u>Miscanthus species</u>	Eulalia Grass
<u>Muehlenbergia species**</u>	Deer Grass
<u>Palmae species</u>	Palms
<u>Picea species</u>	Spruce Trees
<u>Pickeringia Montana**</u>	Chaparral Pea
<u>Pinus species</u>	Pines
<u>Podocarpus species</u>	Fern Pine
<u>Pseudotsuga menziesii</u>	Douglas Fir
<u>Rosmarinus species</u>	Rosemary
<u>Salvia mellifera**</u>	Black Sage
<u>Taxodium species</u>	Cypress
<u>Taxus species</u>	Yew
<u>Thuja species</u>	Arborvitae
<u>Tsuga species</u>	Hemlock
<u>Urtica urens**</u>	Burning Nettle

**\*\* San Diego County native species**

**References:** Gordon, H. White, T.C. 1994. Ecological Guide to Southern California Chaparral Plant Series. Cleveland National Forest.

Willis, E. 1997. San Diego County Fire Chief's Association. Wildland/Urban Interface Development Standards

City of Oceanside, California. 1995. Vegetation Management. Landscape Development Manual. Community Services Department, Engineering Division.

City of Vista, California 1997. Undesirable Plants. Section 18.56.999. Landscaping Design, Development and Maintenance Standards.

[www.bewaterwise.com](http://www.bewaterwise.com). 2004. Fire-resistant California Friendly Plants.

[www.ucfpl.ucop.edu](http://www.ucfpl.ucop.edu). 2004. University of California, Berkeley, Forest Products Laboratory, College of Natural Resources. Defensible Space Landscaping in the Urban/Wildland Interface. A Compilation of Fire Performance Ratings of Residential Landscape Plants.

County of Los Angeles Fire Department. 1998. Fuel Modification Plan Guidelines. Appendix I, Undesirable Plant List, and Appendix II, Undesirable Plant List.

## INVASIVE PLANT LIST

The following species are considered invasive (i.e., those capable of reproducing and spreading into native, non-irrigated areas and displacing those communities). Non-native plant species are prohibited in all areas adjacent to open space lands. Noxious weeds that have been introduced to San Diego County over the years tend to be more widespread and therefore more difficult to contain. The plants listed below have been identified as invasive and/or as noxious weeds and should not be planted or allowed to sprout in any transitional landscapes (landscapes planted with non-native species next to undeveloped areas).

BOTANICAL NAME	COMMON NAME
<u><i>Ailanthus altissima</i></u>	Tree of Heaven
<u><i>Anthemis cotula</i></u> ***	Mayweed, Stinking Chamomile
<u><i>Arctotheca calendola</i></u>	Cape Weed
<u><i>Arundo donax</i></u>	Giant Cane
<u><i>Atriplex semibaccata</i></u>	Australian Saltbush
<u><i>Brassica species</i></u> ***	Mustard
<u><i>Cardaria draba</i></u> ***	Hoary Cress, Perennial Peppergrass
<u><i>Carpobrotus edulis</i></u>	Ice Plant
<u><i>Centaurea solstitialis</i></u>	Yellow Starthistle
<u><i>Cirsium vulgare</i></u> ***	Wild Artichoke
<u><i>Conium maculatum</i></u>	Poison Hemlock
<u><i>Conyza Canadensis</i></u> ***	Horseweed
<u><i>Cortaderia selloana</i></u>	Pampas Grass
<u><i>Cotoneaster lacteus</i></u>	Cotoneaster
<u><i>Cupressus macrocarpa</i></u>	Monterey Cypress
<u><i>Cynara cardunculus</i></u> ***	Artichoke Thistle
<u><i>Cytisus species</i></u>	Scotch Broom, French Broom, etc
<u><i>Elaeagnus angustifolia</i></u>	Russian Olive
<u><i>Eucalyptus globulus</i></u>	Eucalyptus Blue Gum
<u><i>Gensita species</i></u> ***	Broom
<u><i>Hedera helix</i></u>	English Ivy
<u><i>Hypericum perforatum</i></u>	St. John's Wort
<u><i>Ilex aquifolium</i></u>	English Holly
<u><i>Lactuca serriola</i></u> ***	Prickly Lettuce
<u><i>Lepidium latifolium</i></u>	Perennial Pepperweed
<u><i>Myoporum parvifolium</i></u>	Trailing Myoporum
<u><i>Nerium oleander</i></u>	Oleander
<u><i>Nicotiana species</i></u>	Tree Tobacco
<u><i>Olea europaea</i></u>	Olive
<u><i>Pennisetum setaceum</i></u>	Fountain Grass
<u><i>Ricinus communis</i></u>	Castor Bean
<u><i>Robinia pseudoacacia</i></u>	Black Locust
<u><i>Salsola australis</i></u> ***	Russian Thistle, Tumbleweed
<u><i>Schinus molle</i></u>	California Pepper
<u><i>Schinus terebinthifolius</i></u>	Brazilian Pepper
<u><i>Silybum marianum</i></u> ***	Milk Thistle
<u><i>Spartium junceum</i></u>	Spanish Broom

Tamarix species

Ulex europea\*\*\*

Vinca major

Tamarisk

Gorse

Periwinkle


\*\*\* Introduced Weeds to San Diego County

**References:** Bell, Carl, Regional Advisor – Invasive Plants. 2004. University of California Cooperative Extension.


California Exotic Pest Plant Council. October, 1999. Exotic Pest Plants of Greatest Ecological Concern in California. Most Invasive Wildland Pest Plants. [www.caleppc.org/info/99lista.html](http://www.caleppc.org/info/99lista.html).

## **Appendix B**


### **Fire Apparatus Turnaround Configurations**




Private Driveway Hammerhead





Alternate Private Driveway Hammerhead




Private Road or Driveway Cul-de-sac




Private Road Hammerhead



Public Road Cul-de-sac



Hammerhead Incorporating Radius







Turnout—Required for driveways In excess of 300-400'

**\*\*NOT TO SCALE\*\***

**(OVER)**

17



# **Appendix C**

## **Photos**






The north property line



West of the property  
currently under  
development



Northeast of the property  
open space easement



Looking east of the property



Looking to the south on the property



Parcel to the north of the property





The access road to the property



Parcel to the north of the property





Babel Dr

3551 Babel Dr, Jamul, CA 91935

Untitled Placemark

© 2003 Tele Atlas  
Image U.S. Geological Survey

Google

Bonita Vista Way

32°44'19.42" N 116°50'58.68" W

elev 451 m

2003

Eye alt 719 m

## **Appendix D**

### **Behaveplus 4.0.0 Fire Model**





## Inputs: SURFACE, SPOT, IGNITE

Description

Sajady

## Fuel/Vegetation, Surface/Understory

Fuel Model

1

## Fuel/Vegetation, Overstory

Canopy Height

ft

3

## Fuel Moisture

1-h Moisture

%

2

10-h Moisture

%

100-h Moisture

%

Live Herbaceous Moisture

%

Live Woody Moisture

%

## Weather

20-ft Wind Speed (upslope)

mi/h

69

Wind Adjustment Factor

0.40

Air Temperature

oF

100

Fuel Shading from the Sun

%

0

## Terrain

Slope Steepness

%

25

Ridge-to-Valley Elevation Difference

ft

500

Ridge-to-Valley Horizontal Distance

mi

.1

Spotting Source Location

ML

## Run Option Notes

Maximum reliable effective wind speed limit is imposed [SURFACE].

Calculations are only for the direction of maximum spread [SURFACE].

Fireline intensity, flame length, and spread distance are always  
for the direction of the spread calculations [SURFACE].

Wind is blowing upslope [SURFACE].

## Output Variables

Surface Rate of Spread (maximum) (ch/h) [SURFACE]

Heat per Unit Area (Btu/ft<sup>2</sup>) [SURFACE]

Fireline Intensity (Btu/ft/s) [SURFACE]

Flame Length (ft) [SURFACE]

(continued on next page)



## Input Worksheet (continued)

Midflame Wind Speed (upslope) (mi/h) [SURFACE]

Wind Adjustment Factor [SURFACE]

Spot Dist from a Wind Driven Surface Fire (mi) [SPOT]

Probability of Ignition from a Firebrand (%) [IGNITE]

## Notes

--



### Sajady

Surface Rate of Spread (maximum)	665.6 ch/h
Heat per Unit Area	116 Btu/ft <sup>2</sup>
Fireline Intensity	1415 Btu/ft/s
Flame Length	12.7 ft
Midflame Wind Speed (upslope)	27.6 mi/h
Wind Adjustment Factor	0.40
Spot Dist from a Wind Driven Surface Fire	1.2 mi
Probability of Ignition from a Firebrand	100 %





## Discrete Variable Codes Used Sajady .

### Fuel Model

1 Short grass (S)

### Spotting Source Location

ML Midslope, Leeward



## Inputs: SURFACE, SPOT, IGNITE

Description		Sajady
Fuel/Vegetation, Surface/Understory		
Fuel Model		sh5
Fuel/Vegetation, Overstory		
Canopy Height	ft	3
Fuel Moisture		
1-h Moisture	%	2
10-h Moisture	%	3
100-h Moisture	%	
Live Herbaceous Moisture	%	
Live Woody Moisture	%	50
Weather		
20-ft Wind Speed (upslope)	mi/h	69
Wind Adjustment Factor		0.40
Air Temperature	oF	100
Fuel Shading from the Sun	%	0
Terrain		
Slope Steepness	%	25
Ridge-to-Valley Elevation Difference	ft	500
Ridge-to-Valley Horizontal Distance	mi	.1
Spotting Source Location		ML

## Run Option Notes

Maximum reliable effective wind speed limit is imposed [SURFACE].

Calculations are only for the direction of maximum spread [SURFACE].

Fireline intensity, flame length, and spread distance are always  
for the direction of the spread calculations [SURFACE].

Wind is blowing upslope [SURFACE].

## Output Variables

Surface Rate of Spread (maximum) (ch/h) [SURFACE]

Heat per Unit Area (Btu/ft<sup>2</sup>) [SURFACE]

Fireline Intensity (Btu/ft/s) [SURFACE]

Flame Length (ft) [SURFACE]

(continued on next page)



## Input Worksheet (continued)

Midflame Wind Speed (upslope) (mi/h) [SURFACE]

Wind Adjustment Factor [SURFACE]

Spot Dist from a Wind Driven Surface Fire (mi) [SPOT]

Probability of Ignition from a Firebrand (%) [IGNITE]

## Notes

--



## Sajady

Surface Rate of Spread (maximum)	834.6 ch/h
Heat per Unit Area	2068 Btu/ft <sup>2</sup>
Fireline Intensity	31636 Btu/ft/s
Flame Length	52.9 ft
Midflame Wind Speed (upslope)	27.6 mi/h
Wind Adjustment Factor	0.40
Spot Dist from a Wind Driven Surface Fire	3.4 mi
Probability of Ignition from a Firebrand	100 %



## Discrete Variable Codes Used Sajady

### Fuel Model

sh5 High load, dry climate shrub (S) (145)

### Spotting Source Location

ML Midslope, Leeward



## **Appendix E**

### **Street Name Change Letter**



JW 1342

2/11/09

Sigaly  
TPM



**ERIC GIBSON**  
DIRECTOR

## County of San Diego

### DEPARTMENT OF PLANNING AND LAND USE

5201 RUFFIN ROAD, SUITE B, SAN DIEGO, CALIFORNIA 92123-1666  
INFORMATION (858) 694-2360  
TOLL FREE (800) 411-0017  
[www.sdcountry.ca.gov/dplu](http://www.sdcountry.ca.gov/dplu)

August 11, 2009

To: Rusty Otten

From: Nora Rivera  
Land Use Technician III

Subject: Jamul Vistas Drive

Per our conversation, "Jamul Vistas Drive" does no longer exist. It was changed to "Babel Drive", on May 15, 2009.

If you have more questions please call at 858-694-3797.

---

## **Appendix F**

### **Project Facility Availability Fire**



# PROJECT FACILITY AVAILABILITY FORM

FIRE

Please type or use pen

MUCHTAR SAJADY (612) 716-3617  
Owner's Name Phone

10482 MISSISSIPPI BLVD.  
Owner's Mailing Address Street

COON RAPIDS MN 55433  
City State Zip

ORG \_\_\_\_\_

ACCT \_\_\_\_\_

ACT \_\_\_\_\_

TASK \_\_\_\_\_

DATE \_\_\_\_\_ AMT \$ \_\_\_\_\_

DISTRICT CASHIER'S USE ONLY

## SECTION 1. PROJECT DESCRIPTION

## TO BE COMPLETED BY APPLICANT

- A. ☐ Major Subdivision (TM) ☐ Specific Plan or Specific Plan Amendment  
☒ Minor Subdivision (TPM) ☐ Certificate of Compliance: \_\_\_\_\_  
☐ Boundary Adjustment  
☐ Rezone (Reclassification) from \_\_\_\_\_ to \_\_\_\_\_ zone.  
☐ Major Use Permit (MUP), purpose: \_\_\_\_\_  
☐ Time Extension ... Case No. \_\_\_\_\_  
☐ Expired Map ... Case No. \_\_\_\_\_  
☐ Other \_\_\_\_\_

- B. ☒ Residential ..... Total number of dwelling units 3  
☐ Commercial ..... Gross floor area \_\_\_\_\_  
☐ Industrial ..... Gross floor area \_\_\_\_\_  
☐ Other ..... Gross floor area \_\_\_\_\_

C. Total Project acreage 8.0 Total lots 3 Smallest proposed lot 2.12 ac.

Assessor's Parcel Number(s)  
(Add extra if necessary)

5	1	9

0	9	4

1	6

Thomas Bros. Page 1273 Grid A-6

Project address 3551 JAMUL VISTAS DR.  
Street  
JAMUL 91935  
Community Planning Area/Subregion Zip

OWNER/APPLICANT AGREES TO COMPLETE ALL CONDITIONS REQUIRED BY THE DISTRICT.

Applicant's Signature: R. Uoh AS AGENT FOR OWNER Date: 3/13/07

Address: 5725 KEARNY VILLARD, STED, SD, CA 92123 Phone: (858) 571-0555  
(On completion of above, present to the district that provides fire protection to complete Sections 2 and 3 below.)

## SECTION 2. FACILITY AVAILABILITY

## TO BE COMPLETED BY DISTRICT

District name: San Diego Rural Fire Protection Dist

Indicate the location and distance of the primary fire station that will serve the proposed project: Station 66  
+ 4 miles

- A. ☒ Project is in the District and eligible for service.  
☐ Project is not in the District but is within its Sphere of Influence boundary, owner must apply for annexation.  
☐ Project is not in the District and not within its Sphere of Influence boundary.  
☐ Project is not located entirely within the District and a potential boundary issue exists with the \_\_\_\_\_ District.  
B. ☒ Based on the capacity and capability of the District's existing and planned facilities, fire protection facilities are currently adequate or will be adequate to serve the proposed project. The expected emergency travel time to the proposed project is 5 minutes.  
☐ Fire protection facilities are not expected to be adequate to serve the proposed development within the next five years.  
C. ☐ District conditions are attached. Number of sheets attached: \_\_\_\_\_  
☒ District will submit conditions at a later date.

## SECTION 3. FUELBREAK REQUIREMENTS

Note: The fuelbreak requirements prescribed by the fire district for the proposed project do not authorize any clearing prior to project approval by the Department of Planning and Land Use.

- ☒ Within the proposed project 100 feet of clearing will be required around all structures.  
☒ The proposed project is located in a hazardous wildland fire area, and additional fuelbreak requirements may apply. Environmental mitigation requirements should be coordinated with the fire district to ensure that these requirements will not pose fire hazards.

This Project Facility Availability Form is valid until final discretionary action is taken pursuant to the application for the proposed project or until it is withdrawn, unless a shorter expiration date is otherwise noted.

Deborah Bowers Inspector (619) 669-1188 3/26/07  
Authorized signature Print name and title Phone Date

On completion of Sections 2 and 3 by the District, applicant is to submit this form with application to:  
Zoning Counter, Department of Planning and Land Use, 5201 Ruffin Road, Suite B, San Diego, CA 92123

# **Appendix G**

## **TM 5213 RPL-1 Map**




JN 1312

### GENERAL NOTES

- A PERMIT SHALL BE OBTAINED FROM THE COUNTY DEPARTMENT OF PUBLIC WORKS FOR ANY WORK WITHIN THE STREET RIGHT-OF-WAY.
- THE STRUCTURAL SECTION SHALL BE IN ACCORDANCE WITH SAN DIEGO COUNTY STANDARDS AND AS APPROVED BY THE MATERIALS LABORATORY. THE DEVELOPER SHALL BE RESPONSIBLE TO INFORM THE COUNTY MATERIALS LAB PRIOR TO THE TEST.
- APPROVAL OF THESE IMPROVEMENT PLANS AS SHOWN DOES NOT CONSTITUTE APPROVAL OF ANY CONSTRUCTION OUTSIDE THE PROJECT BOUNDARY.
- ALL UNDERGROUND UTILITIES AND LATERALS WITHIN THE STREET RIGHT-OF-WAY SHALL BE CONSTRUCTED, CONNECTED AND TESTED PRIOR TO CONSTRUCTION OF DIKE, CURB, CROSS GUTTER AND PAVING.
- THE EXISTENCE AND LOCATION OF EXISTING UNDERGROUND FACILITIES SHOWN ON THESE PLANS WERE OBTAINED BY A SEARCH OF THE AVAILABLE RECORDS TO THE BEST OF OUR KNOWLEDGE. THERE ARE NO OTHER EXISTING FACILITIES EXCEPT AS SHOWN ON THESE PLANS. HOWEVER, THE CONTRACTOR IS REQUIRED TO TAKE PRECAUTIONARY MEASURES TO PROTECT ANY EXISTING FACILITIES SHOWN HEREON AND ANY OTHER WHICH IS NOT OF RECORD OR NOT SHOWN ON THESE PLANS.
- LOCATION AND ELEVATION OF IMPROVEMENTS TO BE MET BY WORK TO BE DONE SHALL BE CONFIRMED BY FIELD MEASUREMENTS PRIOR TO CONSTRUCTION OF NEW WORK. CONTRACTOR WILL MAKE EXPLORATORY EXCAVATIONS AND LOCATE EXISTING UNDERGROUND FACILITIES SUFFICIENTLY AHEAD OF CONSTRUCTION TO PERMIT REVISIONS TO PLANS IF REVISIONS ARE NECESSARY BECAUSE OF ACTUAL LOCATION OF EXISTING FACILITIES.
- THE CONTRACTOR SHALL NOTIFY THE SAN DIEGO GAS & ELECTRIC COMPANY PRIOR TO STARTING WORK WITH NEAR COMPANY FACILITIES AND SHALL COORDINATE HIS WORK WITH COMPANY REPRESENTATIVES. NOTICE: ALL ELECTRICAL AND GAS SERVICES WITHIN THIS PROJECT ARE "UNDERGROUND INSTALLATIONS". FOR LOCATION OF ELECTRICAL CABLES AND GAS PIPING AND APPURTENANCES CONTACT THE SAN DIEGO GAS & ELECTRIC COMPANY. TELEPHONE: 1-800-422-4133.
- THE CONTRACTOR SHALL NOTIFY THE PACIFIC BELL TELEPHONE COMPANY PRIOR TO STARTING WORK WITH NEAR COMPANY FACILITIES AND SHALL COORDINATE HIS WORK WITH COMPANY REPRESENTATIVES. NOTICE: ALL TELEPHONE SERVICES WITHIN THIS PROJECT BOUNDARY ARE "UNDERGROUND INSTALLATIONS". FOR LOCATION OF CABLES AND APPURTENANCES, CONTACT THE PACIFIC BELL TELEPHONE COMPANY. TELEPHONE: 1-800-422-4133.
- IT SHALL BE THE RESPONSIBILITY OF THE DEVELOPER TO CONTACT THE UTILITY AGENCIES, ADVISE THEM OF THE PROPOSED IMPROVEMENTS, AND BEAR THE COST OF RELOCATIONS, IF NEEDED.
- ALL TELEVISION SERVICES WITHIN THIS PROJECT ARE "UNDERGROUND INSTALLATIONS". FOR LOCATION OF CABLES AND APPURTENANCES, CONTACT: COX CABLE (CATV) TELEPHONE: 1-800-422-4133. SOUTHWESTERN CABLE (CATV) TELEPHONE: 1-800-422-4133.
- ALL ELEVATIONS SHOWN IN PARENTHESES ON EXISTING STREETS ARE FROM FIELD SURVEYS BY: K & S ENGINEERING.
- FINISHED GRADING SHALL BE CERTIFIED BY A REGISTERED CIVIL ENGINEER AND INSPECTED BY COUNTY ENGINEER FOR DRAINAGE CLEARANCE.
- ALL SIGNS SHALL BE ALUMINUM WITH ENGINEER GRADE REFLECTIVE SHEETING, EXCEPT FOR THE FOLLOWING WHICH SHALL HAVE HIGH DENSITY REFLECTIVE SHEETING: R1, R1-2, W1, W2, W3, W4, W5, W6, W11, W14, W17, W20, W26, W27, AND, W81.
- CONTRACTOR AGREES THAT HE SHALL ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THIS PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY; THAT THIS REQUIREMENT SHALL APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS; AND THAT THE CONTRACTOR SHALL DEFEND, INDEMNIFY AND HOLD THE OWNER AND THE ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL AND ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXCEPT FOR LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF THE OWNER OR THE ENGINEER.
- ALL STRIPPING AND SANDBLASTING OF REDUNDANT STRIPING TO BE DONE BY CONTRACTOR.
- NO PAVING SHALL BE DONE UNTIL EXISTING POWER POLES ARE RELOCATED OUTSIDE THE AREAS TO BE PAVED.
- PRIVATE ROAD IMPROVEMENTS SHOWN HEREON ARE FOR INFORMATION ONLY. COUNTY OFFICIALS SIGNATURE HEREON DOES NOT CONSTITUTE APPROVAL OR RESPONSIBILITY OF ANY KIND FOR THE DESIGN OR CONSTRUCTION OF THESE PRIVATE IMPROVEMENTS.
- CONTRACTOR WILL BE RESPONSIBLE FOR THE REPLACEMENT OF ANY STRIPING OR PAVEMENT MARKERS OR LEGENDS OBLITERATED BY THE CONSTRUCTION OF THIS PROJECT.
- CONSTRUCT PUBLIC STREET LIGHT SYSTEM CONFORMING TO SAN DIEGO COUNTY STANDARDS AND STREET LIGHT SPECIFICATIONS. POWER SOURCES AND RUNS SERVING STREET LIGHTS SHALL BE SHOWN ON THE "AS BUILT" IMPROVEMENT DRAWINGS. ALL SOURCES SHALL BE LOCATED WITHIN THE DEDICATED RIGHT OF WAY OR WITHIN EASEMENTS DEDICATED TO THE COUNTY OF SAN DIEGO.
- ALL CUT AND FILL SLOPES OVER THREE (3) FEET CREATED BY GRADING FOR STREETS AND DRIVEWAYS SHALL BE HYDROSEEDED WITH SAN DIEGO COUNTY APPROVED HYDROSEED MIXTURE. HYDROSEEDED SLOPES SHALL BE IRRIGATED BY WATER TRUCK UNTIL THE MIXTURE GERMINATES AND GROWTH IS ESTABLISHED.
- ALL INTERSECTING ROADS AND DRIVEWAYS SHALL BE GRADED AND/OR RECONSTRUCTED, AS REQUIRED, TO MATCH NEW IMPROVEMENTS AND PROVIDE SMOOTH TRANSITION.
- C.M.P. STORM DRAINS SHALL BE CERTIFIED BY THE DEVELOPER'S SOILS ENGINEER TO HAVE A 50 YEAR SERVICE LIFE FOR THE PARTICULAR SOIL AND LOCATION SHOWN ON THE PLANS. THIS CERTIFICATION SHALL BE MADE PRIOR TO THE INSTALLATION OF THE STORM DRAIN.





### REFERENCE DRAWINGS

TPM 15843 IMPROVEMENT PLANS  
TM 4724-1 IMPROVEMENT PLAN  
TM 4187 GRADING & IMPROVEMENT PLANS  
TM 4187 GRADING & IMPROVEMENT PLANS



## COUNTY OF SAN DIEGO TRACT NO. 5213 RPL-1

### JAMUL VISTA ESTATES



### NOTIFICATIONS

- THE EXISTENCE AND LOCATION OF UNDERGROUND UTILITY PIPES AND STRUCTURES SHOWN ON THESE PLANS WERE OBTAINED BY A SEARCH OF AVAILABLE RECORDS. TO THE BEST OF OUR KNOWLEDGE, THERE ARE NO EXISTING UTILITIES EXCEPT AS SHOWN HEREON. HOWEVER, THE CONTRACTOR IS REQUIRED TO TAKE DUE PRECAUTIONARY MEASURES TO PROTECT ANY EXISTING UTILITIES OR STRUCTURES LOCATED AT THE WORK SITE. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CONTACT THE UNDERGROUND SERVICE ALERT (PHONE: 1-800-422-4133) TWO WORKING DAYS IN ADVANCE OF ANY EXCAVATION FOR THE MARK-OUT OF THE LOCATION OF UTILITIES AND NOTIFICATION OF CONSEQUENCE OF WORK.
- FOR ANY QUESTIONS REGARDING THE MARK-OUT OF UNDERGROUND UTILITIES, THE CONTRACTOR SHALL CONTACT THE RESPECTIVE UTILITY COMPANY.
- CONTRACTOR SHALL MAKE EXPLORATORY EXCAVATIONS AND LOCATE EXISTING UNDERGROUND FACILITIES SUFFICIENTLY AHEAD OF CONSTRUCTION TO PERMIT REVISIONS TO PLANS IF REVISIONS ARE NECESSARY BECAUSE OF ACTUAL LOCATION OF EXISTING FACILITIES.
- CONTRACTOR SHALL NOTIFY THE COUNTY ENGINEER'S OFFICE 48 HOURS PRIOR TO BEGINNING ANY WORK ON THIS PROJECT. PHONE: (619) 694-3165.
- THE CONTRACTOR SHALL GIVE 24 HOURS NOTICE ON CALLS FOR INSPECTION. PHONE: (619) 694-3165. ALL WORK PERFORMED WITHOUT BENEFIT OF INSPECTION WILL BE SUBJECT TO REJECTION AND REMOVAL.

### EARTHWORK QUANTITIES

CUT - 2.1 FOR MINOR SLOPES, 2.1 FOR MAJOR SLOPES  
FILL - 2.1  
EXCAVATION: 20,073 CUBIC YARDS (NO UNDERCUT INCLUDED)  
FILL: 1,392 CUBIC YARDS EXPORT: 15,681 CUBIC YARDS  
(NOTE: A SEPARATE VALID PERMIT MUST EXIST FOR EITHER WASTE OR IMPORT AREAS)

### EARTHWORK QUANTITIES NOTE

EARTHWORK QUANTITIES SHOWN ARE FOR ESTIMATING PURPOSES ONLY. ACTUAL QUANTITIES MAY VARY WITH SHRINKAGE, LOSSES DUE TO CLEARING OPERATIONS, COMPACTION, SETTLEMENT, ETC. CONTRACTOR SHOULD VERIFY QUANTITIES PRIOR TO BIDDING.

### SHEET INDEX

SHEET 1	TITLE SHEET	SHEET 10	JAMUL VISTAS DR. PLAN & PROFILE
SHEET 2	SLEEP WILLOW LANE, PLAN & PROFILE	SHEET 11	JAMUL VISTAS DR. PLAN & PROFILE
SHEET 3	SLEEP WILLOW LANE, PLAN & PROFILE	SHEET 12	SKYLINE TRUCK TRAIL, PLAN & PROFILE
SHEET 4	DROPSSEED TERRACE, PLAN & PROFILE	SHEET 13	SKYLINE TRUCK TRAIL, PLAN & PROFILE
SHEET 5	MOOSEWOOD STREET, PLAN & PROFILE	SHEET 14	SKYLINE TRUCK TRAIL, STRIPING PLAN
SHEET 6	WATERMAIN LINE B, PLAN & PROFILE	SHEET 15	EROSION CONTROL PLAN
SHEET 7	WATERMAIN LINE B, PLAN & PROFILE	SHEET 16	EROSION CONTROL PLAN
SHEET 8	WATERMAIN LINE A, PLAN & PROFILE	SHEET 17	EROSION CONTROL PLAN, NOTES & DETAILS
SHEET 9	WATERMAIN LINE A, PLAN & PROFILE	SHEET 18	OSG ENGINEERS MULTI-PLATE ARCH PLANS, TITLE SHEET/INDEX
		SHEET 19	PLAN NEW PROFILE AND FOOTING
		SHEET 20	INLET HEADWALL DESIGN
		SHEET 21	OUTLET HEADWALL DESIGN
		SHEET 22	SPECIFICATIONS

OTAY WATER DISTRICT	
WD 9642	LD 9
PLP-04-008	PZ 1485
3/3/05	11/3/05
11/3/05	11/3/05

FIRE AGENCY	
RURAL FIRE PROTECTION DISTRICT	
REVIEWED BY: D. N.	DATE: 11-3-2005

COUNTY OF SAN DIEGO	
DEPARTMENT OF PUBLIC WORKS	
APPROVED FOR CONSTRUCTION	DATE: 11/3/05

### LEGEND

- OPEN SPACE EASEMENT
- NOISE PROTECTION EASEMENT
- FIRE HYDRANT
- STREET NAME SIGN
- WATER SERVICE
- WATERMAIN
- BLOCK NUMBER
- PERMANENT OPEN SPACE
- FENCING LOCATION

### WORK TO BE DONE

THE IMPROVEMENTS CONSIST OF THE FOLLOWING WORK TO BE DONE IN ACCORDANCE WITH THESE PLANS. THE CURRENT COUNTY OF SAN DIEGO STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION AND SPECIAL PROVISIONS, THE CURRENT SAN DIEGO REGIONAL STANDARDS DRAWINGS, THE CURRENT GRADING ORDINANCES FOR DESIGN AND CONSTRUCTION STANDARDS OF THE COUNTY OF SAN DIEGO AND THE W.A.S. ANY CHANGES OR REVISIONS THEREFROM SHALL BE APPROVED BY THE COUNTY ENGINEER PRIOR TO ANY REQUEST FOR INSPECTION.

### LEGEND

#### STREET

- AC PAVING (PER GENERAL NOTE 2)
- P.C.D. DRIVEWAY
- 6" CURB & GUTTER, TYPE 'C'
- AC DIKE, TYPE 'A'
- PRIVATE DRIVEWAY (SIZE PER PLAN)
- STREET NAME SIGN
- PERMANENT OPEN SPACE BARRIER FENCE
- METAL BEAM GUARD RAILING

#### WATER

- 12" PVC WATERMAIN
- 12" RSGV
- FIRE HYDRANT
- 2" AIR & VACUUM RELEASE VALVE
- 2" BLOW OFF
- CONC THURST BLOCK
- 1" WATER SERVICE LATERAL


#### DRAINAGE

- STORM DRAIN PIPE (HDPPE, (SIZE PER PLAN)
- CONC BROW DITCH (TYPE PER PLAN)
- WING TYPE HEADWALL
- RIP RAP ENERGY DISSIPATOR (TYPE & SIZE PER PLAN)
- EXISTING STORM DRAIN
- CORRUGATED STEEL PIPE INLET

### SDRSD NO.

- SEE SECTION A-A, SHEET NO. 2
- SDRSD G-2
- SDRSD G-3
- DS-7
- DS-13
- CALTRANS A77E1&E2
- WP-01,02
- WP-01
- WT-01
- WA-01,01,03
- WB-01,04
- WT-01
- WS-01
- SDRSD D-75
- SDRSD D-34
- SDRSD D-40
- SDRSD D-16

### SYMBOL



### ASSESSORS PARCEL

519-093-36

### SITE ADDRESS

SKYLINE TRUCK TRAIL, JAMUL, CALIFORNIA

### DECLARATION OF RESPONSIBLE CHARGE

I HEREBY DECLARE THAT I AM THE ENGINEER OF WORK FOR THIS PROJECT, THAT I HAVE EXERCISED RESPONSIBLE CHARGE OVER THE DESIGN OF THE PROJECT AS DEFINED IN SECTION 6703 OF THE BUSINESS AND PROFESSIONS CODE, AND THAT THE DESIGN IS CONSISTENT WITH CURRENT STANDARDS.

I UNDERSTAND THAT THE CHECK OF PROJECT DRAWINGS AND SPECIFICATIONS BY THE COUNTY OF SAN DIEGO AND THE OTAY WATER DISTRICT IS CONFINED TO A REVIEW ONLY AND DOES NOT RELIEVE ME, AS ENGINEER OF WORK, OF MY RESPONSIBILITIES FOR PROJECT DESIGN.

KAMAL S. SWERS, R.C.E. 48592 EXP. 06/03/06

11/3/05 DATE

### OWNER'S CERTIFICATE

IT IS AGREED THAT FIELD CONDITIONS MAY REQUIRE CHANGES TO THESE PLANS. IT IS FURTHER AGREED THAT OWNER (DEVELOPER) SHALL HAVE A REGISTERED CIVIL ENGINEER MAKE SUCH CHANGES, ALTERATIONS, OR ADDITIONS TO THESE PLANS WHICH THE DIRECTOR OF PUBLIC WORKS DETERMINES TO BE NECESSARY AND DESIRABLE FOR THE PROPER COMPLETION OF THE IMPROVEMENTS. I FURTHER AGREE TO COME IN PERSON ON ANY IMPROVEMENTS SHOWN ON THESE PLANS WITHIN EXISTING COUNTY RIGHT-OF-WAY WITHIN 60 DAYS AFTER ISSUANCE OF THE CONSTRUCTION PERMIT AND TO PURSUE SUCH WORK ACTIVELY ON EVERY NORMAL WORKING DAY UNTIL COMPLETED, IRRESPECTIVE AND INDEPENDENT OF ANY OTHER WORK ASSOCIATED WITH THIS PROJECT OR UNDER MY CONTROL.

OWNER: RANDY SMITH  
ADDRESS: 1735 MALLOW COURT  
CARLSBAD, CA 92009  
TELEPHONE: (760) 438-7940 (FAX) 760-438-1739  
AUTHORIZED NAME: RANDY SMITH

### WATER NOTES

SEE SHEET NO. 2


PERMITS	
ADMINISTRATIVE PERMIT NO.	N/A
REZONE PERMIT NO.	N/A
GRADING PLAN NO.	L-15672
SPECIAL USE PERMIT NO.	N/A
TITLE MAP NO.	5213 RPL-1
NO. 2	9373337
BENCH MARK	
DESCRIPTION: COUNTY B.M. # J.M. 0185	
LOCATION: IN CHURCHVIEW AT THE INTERSECTION OF LYONS VALLEY RD. & JAMUL RD.	
RECORD FROM: SAN DIEGO VERTICAL CONTROL	
ELEVATION: 1024.076 DATUM: U.S.C. & G.S.	

### PRIVATE CONTRACT

SHEET 1	COUNTY OF SAN DIEGO	22
DEPARTMENT OF PUBLIC WORKS		
PLANS FOR THE IMPROVEMENT OF:		
COUNTY OF SAN DIEGO TRACT NO. 5213 RPL-1		
TITLE SHEET		
CALIFORNIA COORDINATE INDEX: 206-1809		
Drawn by: 3/3/05	Checked by: 11/3/05	TM
Scale: 1"=40'	Scale: 1"=40'	5213-1

ENGINEER'S NAME: K & S ENGINEERING PHONE NO: (619) 226-5585

K&S ENGINEERING  
Planning Engineering Surveying  
(619) 296-5565 7801 Mission Center Court, Suite 100  
San Diego, CA 92108



OTAY WATER DISTRICT  
WD 9642 ID 9  
PZ 1485  
REVIEWED BY: *Frank T. Clark* DATE: 4/3/05

ENGINEER OF WORK  
KAMAL S. SWEIS RCE 48592 DATE: 11/3/05



COUNTY APPROVED CHANGES		
No.	Description	Approved by Date:

BENCH MARK  
DESCRIPTION: COUNTY B.M. # J.W. 0185  
LOCATION: IN CHURCHYARD AT THE INTERSECTION OF  
LYONS VALLEY RD. & JAMUL RD.  
RECORD FROM: SAN DIEGO VERTICAL CONTROL  
ELEVATION: 1024.076 DATUM: U.S.C. & G.S.


PRIVATE CONTRACT  
5 COUNTY OF SAN DIEGO DEPARTMENT OF PUBLIC WORKS 22 SHEETS  
PLANS FOR THE IMPROVEMENT OF:  
COUNTY OF SAN DIEGO TRACT NO. 5213 RPL-1  
MOOSEWOOD STREET PRIVATE ROAD PER 3.1.c  
CALIFORNIA COORDINATE INDEX 206-1809  
Recommended for approval: N/A  
Approved: PRIVATE ROAD, SEE ABOVE  
Checked by: TM 5213-1  
WO 9642 PLP-04-008

Note:  
Restrict all brushing, clearing and/or grading such that none will be allowed within 300 feet of Coastal Sage brush habitat during the breeding season of the California Gnatcatcher. This is defined as occurring between March 1 and August 15. The Director of Planning and Land Use, may waive this condition, through written concurrence from the United States Fish and Wildlife Service and the California Department of Fish and Game, that no California Gnatcatchers are present in the vicinity of the brushing, clearing or grading.

CENTERLINE DATA		
NO.	DELTA OR BRG. RADIUS LENGTH	REMARKS
1	N23°01'40"W 31.83'	CENTERLINE
2	D=18°02'03"W 100.00'	CENTERLINE
3	N01°58'42"W 195.90'	CENTERLINE

CURB DATA		
NO.	DELTA OR BRG. RADIUS LENGTH	REMARKS
1	D=131°20'57" 10' 22.92'	CURB & GUTTER, TYPE G (G-2)
2	D=09°50'47" 08' 15.12'	CURB & GUTTER, TYPE G (G-2)
3	N01°58'42"W 195.90'	CURB & GUTTER, TYPE G (G-2)
4	D=21°23'50" 112' 195.90'	CURB & GUTTER, TYPE G (G-2)
5	D=60°47'58" 28' 41.42'	CURB & GUTTER, TYPE G (G-2)
6	D=60°47'58" 28' 29.71'	CURB & GUTTER, TYPE G (G-2)
7	D=90°01'52" 30' 47.14'	CURB & GUTTER, TYPE G (G-2)

WATER DATA		
NO.	DELTA OR BRG. RADIUS LENGTH	REMARKS
1	N43°00'18"E 26.00'	12" PVC CL200, C900 DR14
2	N01°58'42"W 221.47'	12" PVC CL200, C900 DR14
3	D=08°16'02"W 1229.00'	12" PVC CL200, C900 DR14



JAMUL VISTA ESTATES  
ENGINEER'S NAME: K & S ENGINEERING PHONE NO. (619) 296-5565  
DATE: 10/31/2005 11:59:48 AM P15

# Appendix H

## Vegetation Map

# Biological Resources

The Sajady Subdivision Project  
APN 519-094-16

## LEGEND

- Diegan Coastal Sage Scrub (Holland Code #32500)
- Urban/Developed (Holland Code #12000)
- Orange-throated Whitetail

Not Shown:  
San Diego County Vigiera (co-dominant in the CSS)

Prepared by:



VINCENT N. SCHEIDT, MA  
CERTIFIED BIOLOGICAL CONSULTANT

3170 Occidental Street • San Diego, CA 92122 • (619) 457-3073

OWNER:  
MUHTAR SAJADY AND  
FATIMA SAJADY  
10482 MISSISSIPPI BLVD.  
COON RAPIDS, MN 55433  
(612) 716-3617

PROJECT ADDRESS:  
3551 JAMUL VISTAS DRIVE  
JAMUL, CA

APN:  
519-094-16


LEGAL DESCRIPTION:  
PARCEL 3 OF PARCEL MAP 7076

SOURCE OF EXISTING TOPOGRAPHY:  
COUNTY 200 SCALE TOPOGRAPHIC  
SURVEY SHEET 206-1815,  
PHOTOGRAPHY DATED: MAY 1981

PREPARED BY:



**CREW ENGINEERING  
AND SURVEYING**  
5725 KEARNY VILLA ROAD, STE. "D"  
SAN DIEGO, CA 92123  
(619) 571-0555

RONALD C. ASHMAN  
RCE 34300 EXPIRES: SEPT. 30, 2007



## PRELIMINARY GRADING PLAN JAMUL VISTAS DRIVE (JAMUL)

DATE: 11/01/06
SCALE: 1"=40'
DRAWN: S.G.
APPROVED: R.A.
JOB: 1342
SHEET: 1 OF 1



VICINITY MAP  
NOT TO SCALE  
T.B.; 1273, A-6

- (A) EXISTING 40' L.O.D. GRANTED TO THE COUNTY OF SAN DIEGO PER DOC. 78-087975; REC. MARCH 6, 1978 OF O.R.
- (B) EXIST. 40' ROAD AND UTILITY EASEMENT PER INST. 86-141647; REC. APRIL 11, 1986 OF O.R.
- (C) EXIST. 40' OTAY WATER EASEMENT PER INST. 88-307582; REC. JUNE 27, 1988 OF O.R.
- (D) EXIST. 40' SDG&E PUBLIC UTILITY EASEMENT PER INST. 1991-0089779; REC. MARCH 1, 1991 OF O.R.
- (E) EXIST. 40' PACIFIC BELL PUBLIC UTILITY EASEMENT PER INST. 90-636036; REC. NOVEMBER 29, 1990 OF O.R.
- (F) OPEN SPACE EASEMENT GRANTED TO THE COUNTY OF SAN DIEGO PER DOC. NO. 2005-0866579, REC. OCTOBER 4, 2005.
- (G) FIRE CLEARING EASEMENT GRANTED TO THE COUNTY OF SAN DIEGO PER DOC. NO. 2005-0866580, REC. OCTOBER 4, 2005.
- (H) FIRE CLEARING EASEMENT GRANTED TO THE COUNTY OF SAN DIEGO PER PARCEL MAP 18704.
- (I) I.O.D. IN FAVOR OF SAN DIEGO COUNTY FOR FUEL BREAK RECORDED MAY 3, 1973 AS FILE NO. 73-004818 OF OFFICIAL RECORDS.

# **Appendix I**

## **Otay Water District Flow Letter**



JUN-01-2000 06:33AM FROM-

T-061 P.001/006

F-100

JN 1342

6/1/09


Seyndy  
TPM

**OTAY WATER DISTRICT**  
**2554 SWEETWATER SPRINGS BLVD**  
**SPRING VALLEY, CA 91978**  
**PH: (619) 670-2241**  
**FAX: (619) 670-6184**

**FACSIMILE TRANSMITTAL SHEET**

TO:	FROM:
Rusty Otten	Tanya Romero
COMPANY:	DEPARTMENT:
Crew Engineering and Surveying	Public Services Engineering
FAX NUMBER:	TOTAL NO. OF PAGES INCLUDING COVER:
(858) 571-0562	6
DATE:	
6/1/09	
OTAY PERMIT(S):	
n/a	
<input type="checkbox"/> Urgent <input checked="" type="checkbox"/> For Review <input type="checkbox"/> Please Comment <input type="checkbox"/> Please Reply <input type="checkbox"/> For Your Information	
NOTES/COMMENTS:	

T-081 P.002/006 F-188



JUN-01-2009 08:34AM FROM-

T-061 P.003/006 F-100



...Dedicated to Community Service

2854 SWEETWATER SPRINGS BOULEVARD, SPRING VALLEY, CALIFORNIA 91975-2034  
TELEPHONE: 670-2222, AREA CODE 619  
www.otaywater.gov

June 1, 2009

Project: p1438-030000  
Activity: 3104Attention: Rusty Otten  
Crew Engineering and Surveying  
5725 Kearny Villa Rd., Suite D.  
San Diego, CA 92123

SUBJECT: Fire flow calculations for 3551 Jamul Vistas Dr., APN: 519-094-16-00

Mr. Otten:

Fire flow calculations for the subject site were performed by District staff using MWH Soft, Inc., H<sub>2</sub>O map water, Version 6.0, under the following assumptions:

- The water level in the storage facility at the time of a fire is at the minimum operational level that typically occurs during peak-hour demand conditions.
- The prescribed *two hour* fire duration coincides with a maximum day demand condition.
- Into and out of the pressure zone where a fire is occurring, all Agency booster pumps are off.
- Areas outside the fire circumference in the same pressure zone maintain a minimum pressure of 20 PSI.
- Current static pressure based on hydraulic grade line calculations is: 24.6

The results are as follows:

STATIC PRESSURE:	13.7	PSI (System demand only at maximum day condition)
RESIDUAL PRESSURE:	17.8	PSI (System and fire flow demand of 1500 gallons per minute)
FLOW @ 40 PSI:	(1,634.5)	GPM
FLOW @ 20 PSI:	(791.1)	GPM


A hydrant system curve is also attached for your reference.

Sincerely,

THE OTAY WATER DISTRICT  
ENGINEERING PUBLIC SERVICES

JUN-01-2008 06:34AM FROM-

T-081 P.004/006 F-188



JUN-01-2009 08:38AM FROM-

T-081 P.006/008 P-188



...Dedicated to Community Service

2654 SWEETWATER SPRINGS BOULEVARD, SPRING VALLEY, CALIFORNIA 91979-2004  
TELEPHONE: 679-2222, AREA CODE 619 [www.otaywater.gov](http://www.otaywater.gov)

June 1, 2009

Project: p1438-030000  
Activity: 3104Attention: Rusty Otten  
Crew Engineering and Surveying  
5725 Kearny Villa Rd., Suite D.  
San Diego, CA 92123

SUBJECT: Fire flow calculations for 3551 Jamul Vistas Dr.; APN: 519-094-16-00

Mr. Otten:

Fire flow calculations for the subject site were performed by District staff using MWH Soft, Inc., H<sub>2</sub>O map water, Version 6.0, under the following assumptions:

- a. The water level in the storage facility at the time of a fire is at the minimum operational level that typically occurs during peak-hour demand conditions.
- b. The prescribed *two hour* fire duration coincides with a maximum day demand condition.
- c. Into and out of the pressure zone where a fire is occurring, all Agency booster pumps are off.
- d. Areas outside the fire circumference in the same pressure zone maintain a minimum pressure of 20 PSI.
- e. Current static pressure based on hydraulic grade line calculations is: 41.2

The results are as follows:

STATIC PRESSURE:	31.5	PSI (System demand only at maximum day condition)
RESIDUAL PRESSURE:	37.9	PSI (System and fire flow demand of 2500 gallons per minute)
FLOW @ 40 PSI:	(989.3)	GPM
FLOW @ 20 PSI:	854.6	GPM


A hydrant system curve is also attached for your reference.

Sincerely,

THE OTAY WATER DISTRICT  
ENGINEERING PUBLIC SERVICES


JUN-01-2000 08:35AM FROM-

T-001 P.006/008 F-100



# **Appendix K**

## **Fuel Modification map**



**COUNTY NOTE:**  
THIS PLAN IS PROVIDED TO ALLOW FOR FULL AND ADEQUATE DISCRETIONARY REVIEW OF A PROPOSED DEVELOPMENT PROJECT. THE PROPERTY OWNER ACKNOWLEDGES THAT ACCEPTANCE OR APPROVAL OF THIS PLAN DOES NOT CONSTITUTE AN APPROVAL TO PERFORM ANY GRADING SHOWN HEREON, AND AGREES TO OBTAIN VALID GRADING PERMISSIONS BEFORE COMMENCING SUCH ACTIVITY.

**CONCEPT GRADING NOTE:**  
PAD AND DRIVEWAY GRADING IS PRESENTED FOR INFORMATION ONLY TO FACILITATE THE C.E.Q.A. DISCLOSURE PROCESS. THE APPLICANT PROPOSES A LOT SALES PROJECT AND DOES NOT INTEND TO GRADE INDIVIDUAL BUILDING SITES. THE APPLICANT ACKNOWLEDGES THAT TRACT GRADING OF THE SITE MAY REDEFINE THE PROJECT AND MAY NECESSITATE ADDITIONAL PUBLIC REVIEW.

**APPROXIMATE PAD/DRIVEWAY GRADING QUANTITIES:**  
EXCAVATION: 4900 C.Y.  
EMBANKMENT: 4900 C.Y.  
IMPORT/EXPORT: 0 C.Y.  
MAXIMUM SLOPE HEIGHTS:  
CUT: 15' @ 1 1/2:1  
FILL: 15' @ 2:1

**APPROXIMATE PRIVATE ROAD GRADING QUANTITIES:**  
EXCAVATION: 2850 C.Y.  
EMBANKMENT: 2850 C.Y.  
IMPORT/EXPORT: 0 C.Y.  
MAXIMUM SLOPE HEIGHTS:  
CUT: 10' @ 1 1/2:1  
FILL: 15' @ 2:1


## FUEL MANAGEMENT ZONE LEGEND:

- FMZ1— 50' FROM STRUCTURE
- FMZ2— 100' FROM STRUCTURE




APN: 519-084-18  
LEGAL DESCRIPTION: PARCEL 3 OF PARCEL MAP 7076

SOURCE OF EXISTING TOPOGRAPHY:  
COUNTY 200 SCALE TOPOGRAPHIC SURVEY SHEET 206-1815, PHOTOGRAPHY DATED: MAY 1981

PREPARED BY:  
**CREW ENGINEERING AND SURVEYING**  
5725 KEARNY VILLA ROAD, STE. "D"  
SAN DIEGO, CA 92123  
(858) 571-0555  
RONALD C. ASHMAN  
RCE 34300 EXPIRES: SEPT. 30, 2009



- (A) EXISTING 40' I.O.D. GRANTED TO THE COUNTY OF SAN DIEGO PER DOC. 78-087975; REC. MARCH 6, 1978 OF O.R.
- (B) EXIST. 40' ROAD AND UTILITY EASEMENT PER INST. 86-141647; REC. APRIL 11, 1988 OF O.R.
- (C) EXIST. 40' OTAY WATER EASEMENT PER INST. 86-307582; REC. JUNE 27, 1988 OF O.R.
- (D) EXIST. 40' SDG&E PUBLIC UTILITY EASEMENT PER INST. 1991-0089779; REC. MARCH 1, 1991 OF O.R.
- (E) EXIST. 40' PACIFIC BELL PUBLIC UTILITY EASEMENT PER INST. 90-636036; REC. NOVEMBER 29, 1990 OF O.R.
- (F) OPEN SPACE EASEMENT GRANTED TO THE COUNTY OF SAN DIEGO PER DOC. NO. 2005-0868579, REC. OCTOBER 4, 2005.
- (G) FIRE CLEARING EASEMENT GRANTED TO THE COUNTY OF SAN DIEGO PER DOC. NO. 2005-0868580, REC. OCTOBER 4, 2005.
- (H) FIRE CLEARING EASEMENT GRANTED TO THE COUNTY OF SAN DIEGO PER PARCEL MAP 18704.
- (I) I.O.D. IN FAVOR OF SAN DIEGO COUNTY FOR FUEL BREAK RECORDED MAY 3, 1973 AS FILE NO. 73-004818 OF OFFICIAL RECORDS.



REVISIONS	BY
1. MOVE CONCEPT	TZ
2. BLDG. REL. 2	2/06
3.	
4.	
5.	
6.	
7.	
8.	
9.	
10.	

DATE: 11/01/08
SCALE: 1"=40'
DRAWN: S.G.
APPROVED: R.A.
JOB: 1342
SHEET: 1 OF 1

J.N. 1342